


Contemporary Log Homes

THE $SHERWOOD - 1,559 \ sq.\ ft.$



This is a mountain-type home, styled like a chalet. The roof is a vaulted system in a 12/12 pitch. The upstairs loft makes a very nice master bedroom with its own bath and the storage area becoming a nicely sized closet. The very large windows and high ceilings give The Sherwood an open, woodsy feeling and make the living areas appear quite large.





2ND FLOOR PLAN



THE SHERWOOD MODEL 1ST FLOOR PLAN

1ST FLOOR PLAN 1051 SQ. FT. 2ND FLOOR PLAN 508 SQ. FT. TOTAL LIVABLE 1559 SQ.FT. PORCHES 208 SQ.FT. 1

The Sherwood - 1,559 sq. ft. Material Package Price: \$51,450.00

STANDARD MATERIAL PACKAGE INCLUDES:

SILL PLATE: 2x8 pressure treated or redwood plate.

FLOOR SYSTEM: 2x floor joists with 3/4" T&G OSB or

plywood sheathing & girder beams.

PORCH FLOORS: 2x floor joists with 2x6 decking.

LOG WALLS: 7" dia. Swedish cope, lodge pole pine and

douglas fir mix.

INTERIOR PARTITIONS: 2x4 or 2x6 studs @ 24" o.c.

STAIRS: 2x12 stringers and treads.

LOG GUARDRAILS: 2" dia. pickets @ 5" o.c. with 4" dia. rail on

stairways & 2nd floor balconies

ROOF SYSTEM: 2x roof rafters with 1/2" OSB roof

sheathing (or 5/8" OSB where required by

code).

PORCH ROOF SYSTEM: 2x roof rafters with 1/2" OSB roof

sheathing (or 5/8" OSB where required by

code).

FASCIA: 2x S1S2E spruce or pine with 1x4 shingle

molding.

ROOFING: 30 yr. Architectural fiberglass shingles over

15 lb. roofing felt.

BASIC BUILDING Joist hangers, hurricane ties, roof HARDWARE: straps, log wall bolts & construction

adhesive between each course of logs.

CONSTRUCTION MANUAL: A simple step by step "how-to" guide.

BLUEPRINTS: Five complete sets of permit ready plans

prepared by registered architects.

LOG FINISH MATERIALS: "Sashco" products: Log Jam chinking for

interior & exterior joints/seams.

Capture exterior stain and Cascade exterior clear coat. Symphony (2 coats) interior clear

coat finish.

TECHNICAL ASSISTANCE: A Contemporary Log Home representative

will assist the construction crew at the construction site in starting log walls from

the first floor.

FREIGHT: Included to the construction site if the

materials are paid for prior to shipping in the

AZ, CO, UT areas. Additional freight costs will apply for all other areas.

MANY POPULAR OPTIONS ARE AVAILABLE:

6x8 D-shaped logs

8", 9", 10" & 12" diameter logs

Metal Roofing Window Packages

Heavy Timber Structures

Pre-fitted Natural Hand Hewn Logs

Hand Peeled Machine Logs

Log Stairs Door Packages

S Custom Design by Registered

Architects

Thanks for taking the time to consider us as part of your dream. Call one of our representatives today or anytime. We don't have a clock when it comes to customer service!



Western Region

4542 East McKellips Road

Suite 101

Mesa, AZ 85215 (480) 894-1715

Eastern Region 25950 Hayden Lane Edinboro, PA 16412 (814) 734-8716

Visit us on the web at www.clhllc.com
Email: deliverdreams@clhllc.com